No.	Items of work	Per	Quantity
10	Flooring with 3" jelly concrete in mortar and cement plastering including cutting tiles, etc.	Sqr.	6·54
11	Coping with burnt brick in mortar including plastering, complete	R.ft.	54
12	Teakwood doors with battened shutters, etc., complete ..	S.ft.	225
13	Teakwood windows with battened shutters with iron bars, etc., complete.	,,	48
14	Teakwood ventilators with glazed shutters with iron bars, etc., complete.	,,	36
15	Silicate painting	Sqr.	5·80
16	Jungle wood wrought and put up including wood oiling ..	C.ft.	89·65
17	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	14·98
18	Mangalore ridge tiles set in mortar	R.ft.	155
19	Teakwood eave boards including painting.	,,	235
20	Providing valleys at the commencement of office room with zinc sheets over ⅜" teak planks.	L. S.	..
21	Tarring wall plates and sides of doors, etc.	,,	...
22	Providing stone mortar and pestle	,,	...
23	Do sinks in bath and kitchen	,,	..
24	Constructing seats in latrine, etc.	,,	...
25	Providing 6" dia. chimneys for the escape of smoke in bath and kitchen.	No.	2
26	Providing 2" dia. galvanised iron pipes 2' long and providing hearths, etc.	L. S.	...
27	Providing Mangalore glass tiles ... ,, ...	No.	4
28	Constructing drain with jelly concrete foundation and brick in mortar sides and cement plastering, complete, and constructing a cistern outside to collect waste water	L. S.	...
29	Providing and fixing wall pegs with Honne wood planks 1" thick to keep things.	,,	...
30	Clearing ground, levelling sides and unforeseen works, etc. ...	,,	...

K. VENKATARAMAIYA,
Executive Engineer.

WATER SUPPLY DIVISION.

Abstract Notification dated 23rd—25th October 1930.

The attention of the public is invited to the detailed notification, calling for sealed tenders for laying 4" cast iron delivery and distribution pipes for Water Supply to the Northern Extension and Kuripalya at Tumkur published on page 1350 of Part VI of the *Mysore Gazette*, dated 30th October 1930.

The last day for the receipt of tenders is 14th November 1930.

M. NARASIMHAIYA,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, GAUGING AND UPPER CHANNELS DIVISION, MYSORE.

Notification dated 30th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Gauging and Upper Channels Division, Mysore, up to 5 P.M., on Saturday the 22nd November 1930, for the following items of work :—

(i) Supplying and fixing of teakwood planks over C. D. S. and Devaroy anicuts.
(ii) Packing joints between planks.
(iii) Supplying and fixing needle shutters for the Scouring Sluice in the body wall of Devaroy anicut.

1. An approximate estimate of quantities required is given below with the specification. The work should be completed not later than the end of January 1931. Further information required, if any, may be obtained at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M. on working days.

2. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer.

3. Each tender must be accompanied by a deposit of Rs. 200 either in cash or in Government Promissory Notes as earnest money and be superscribed "Tender for (1) supplying and fixing of teakwood planks over C. D. S. and Devaroy anicuts to be opened at 5 P.M. on 22nd November 1930."

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

6. The name of the successful tenderer will be posted on the Notice Board of the Executive Engineer's Office in due course. No enquiries regarding the acceptance or the rejection of any tender will be received or replied to.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

8. The tenderer must quote specific rates both in words and figures for each item. Quotations like "..... percentage less than the estimate" will not be considered.

(1) Specification for supplying and fixing teakwood planks on C. D. S. and Devaroy anicuts near Krishnarajasagara.

(*a*) The planks are to be of hard, well seasoned teakwood free from rotten or unsound knots or knots in clusters, free from shakes and checks, bore holes or worm holes and free from all defects generally.

(*b*) The planks are to be coated with 2 coats of good tar on all sides.

(*c*) The planks are to be provided with iron straps 1" wide by 1/16" thick nailed firmly to the plank at both ends on either side.

(*d*) The planks should also be fitted with two stiffening flat iron straps 2" wide by 1/8" thick at each end and on both sides of the plank screwed or bolted firmly to the plank.

(*e*) The 12" wide planks should be one piece. The 18" wide planks may be made of two pieces with a horizontal tongued and grooved joint approved by the Executive Engineer. Quotations must be given for both full planks and jointed planks separately.

(*f*) The approximate number and size of planks required are as given below. The planks are to be 1½" thick.

No.	Dimensions		Square foot	Rate
	Length	Breadth		
200	10½'	1½'		
165	10½'	1'		
4	8'	1½'		

(*g*) The planks are to be fixed over the C. D. S. and Devaroy anicuts between the rail uprights fixed for the purpose.

(2) *Packing joints between planks.*—Packing with gunny cloth dipped in tar over the joints of planks and nailing over it 4" strip of old tin so as to prevent leaks. Rate to be quoted by R.ft.

(3) Specification for the supplying and fixing needle shutters for the Scouring Sluice in the body wall of Devaroy anicut.

(*a*) The needle shutters are to be of hard, well seasoned teak free from checks, shakes or knots. This should be free from defects and painted with 2 coats of tar.

(*b*) The needles should be 6' long, 9" wide and 3" thick. The ends shod with iron straps 1½" wide by 1/8" thick all round. These needles should be provided with 4" diameter iron ring at one end.

Approximate quantity required :—

No.	Dimensions in feet			Total in number	Per	Rate
	L.	B.	D.			
9	6	¾	¼	9	Each	

Notification dated 30th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Gauging and Upper Channels Division, Mysore, up to 5 P.M., on Saturday the 22nd November 1930, for the following items of work :—

(i) Supplying and fixing of teakwood planks over C. D. S. and Devaroy anicuts.
(ii) Packing joints between planks.
(iii) Supplying and fixing needle shutters for the Scouring Sluice in the body wall of Devaroy anicut.

1. An approximate estimate of quantities required is given below with the specification. The work should be completed not later than the end of January 1931. Further information required, if any, may be obtained at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M. on working days.

2. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer.

3. Each tender must be accompanied by a deposit of Rs. 200 either in cash or in Government Promissory Notes as earnest money and be superscribed "Tender for (1) supplying and fixing of teakwood planks over C. D. S. and Devaroy anicuts to be opened at 5 P.M., on 22nd November 1930."

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money forfeited.

6. The name of the successful tenderer will be posted on the Notice Board of the Executive Engineer's Office in due course. No enquires regarding the acceptance or the rejection of any tender will be received or replied to.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

8. The tenderer must quote specific rates both in words and figures for each item. Quotations like "..... Percentage less than the estimate" will not be considered.

(1) Specification for supplying and fixing teakwood planks on C. D. S. and Devaroy anicuts near Krishnarajasagara.

(*a*) The planks are to be of hard, well seasoned teakwood free from rotten or unsound knots or knots in clusters, free from shakes and checks, bore holes or worm holes and free from all defects generally.
(*b*) The planks are to be coated with 2 coasts of good tar on all sides.
(*c*) The planks are to be provided with iron straps 1" wide by 1/16" thick nailed firmly to the plank at both ends on either side.
(*d*) The planks should also be fitted with two stiffening flat iron straps 2" wide by 1/8" thick at each end and on both sides of the plank screwed or bolted firmly to the plank.
(*e*) The 12" wide planks should be one piece. The 18" wide planks may be made of two pieces with a horizontal tongued and grooved joint approved by the Executive Engineer. Quotations must be given for both full planks and jointed planks separately.
(*f*) The approximate number and size of planks required are as given below. The planks are to be 1½" thick.

No.	Dimensions		Square foot	Rate
	Length	Breadth		
200	10½"	1½'		
165	10½"	1'		
4	8'	1½'		

(*g*) The planks are to be fixed over the C. D. S. and Devaroy anicuts between the Rail uprights fixed for the purpose.

(2) *Packing Joints—between planks.*—Packing with gunny cloth dipped in tar over the joints of planks and nailing over it 4" strip of old tin so as to prevent leaks. Rate to be quoted by R.ft.

(3) Specification for the supplying and fixing needle shutters for the Scouring Sluice in the body wall of Devaroy anicut.

(*a*) The needle shutters are to be of hard, well seasoned teak, free from checks, shakes or knots. This should be free from defects and painted with 2 coats of tar.

(*b*) The needles should be 6' long, 9" wide and 3" thick. The ends shod with iron straps 1½" wide by 1/8" thick all round. These needles should be provided with 4" diameter iron-ring at one end.

Approximate quantity required.

No.	Dimensions in feet			Total in number	Per	Rate
	L.	B.	D.			
9	6	¾	½	9	Each	

B. KRISHNA RAO,
Executive Engineer.

MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Notification dated 31st October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Open Line Divison, Mysore Railways, Mysore, up to 4 P. M., on Friday the 21st November 1930, from Contractors, who are willing to do the work of construction of a new Smithy Shop at Central Workshops, Mysore.

2. Every tender must be accompanied by an earnest money of Rs. 500 which can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms, which can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of rupee one.

4. Tenders which give rates, as per estimate rates or so much per cent, above or below estimate rates will not be considered.

5. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office by 20th December 1930. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned ass oon as possible after the tenders are disposed of, while that of the successful tenderer will be accepted as part payment towards the security deposit due as per para 7 *infra*.

7. The successful tenderer should deposit with the Auditor, Mysore Railways, Mysore, before they sign the schedule agreement 5 per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the agreement.

8. The final acceptance of the tender will rest with the Engineer-in-Chief, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assinging any reasons therefor, any or all the tenders.

9. Work should be started within two weeks, from the date of acceptence of tender and completed before 15th June 1931, with a guaranteed monthly rate of progress. The ascompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

10. The time limit specified in para 9 should be scrictly adhered to and any violation of this will render the consractor liable to forfeit his 5 per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

11. Plans and specifications and other details of work to be done are available for inspection in the Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

12. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Engineer-in-Chief, will be final and legally binding.